

**Roof Replacement – Building E, F, A  
Dehesa School District  
Summer 2021 Roofing Project**

Addendum #1:

- 1.) Per specifications, Section 1.1, B., #8:
  - a. Edge Metal: Install new Viking KEE Clad Metal, or pre-approved equal, over wood blockers. Contractor responsible to field-verify dimensions.

Addendum #2:

- 2.) Bidding contractors are responsible for full removal and abatement of all existing ACM. Please see ACM Report included in the project Bid Set for locations / quantities of ACM.

Addendum #3:

- 1.) Per specifications, Section 1.1, B., #12:
  - a. Gutters: Install new 22 ga. gutters and downspouts on the front of the building. Downspouts to be installed on each corner. Contractor responsible to field-verify dimensions. The gutters on the back of the building are to remain. Install a new downspout on the corner of the existing gutters where there is currently no downspout. Contractor to match size / profile of the existing downspout. All metal to be fabricated from ***R-Mer SS Flat Stock (Emerald Green)***.